



### Team Details

Shashi Kant Shah– AGM (Lead Process Potline)

Mohammed Ishan– Associate Manager (Lead Electrical Bakeoven)

K V D S Vinay Kumar – Assistant Manager (Energy Cell Coordinator)



## CORE PURPOSE

Vedanta is a globally diversified natural resources company with low cost operations. We empower our people to drive excellence and innovation to create value for our stakeholders. We demonstrate world class standards of governance, safety, sustainability and social responsibility.

## OUR VALUES



TRUST



ENTREPRENUERSHIP



INNOVATION



EXCELLENCE




INTEGRITY



CARE



RESPECT



## Smelter 1

- ✓ GP – 320 Prebake Technology
- ✓ No. of Lines – 2
- ✓ No. of Pots – 608
- ✓ Pot Amperage – 325 KA
- ✓ Design Capacity – 500 KTPA

- ✓ GAP – 2 Paste Plants (Outotec GMBH, Germany)
- ✓ Bake Oven – 4 Bake Furnaces
- ✓ Anode Rodding Plant

- ✓ Ingot Casting Mill – 3 Lines
- ✓ Wire Rod Mill – 2 Lines
- ✓ Billet Casting Mill – 1 Line
- ✓ Slab Casting – 1 Line


## Smelter 2

- ✓ GP – 340 Prebake Technology
- ✓ No. of Lines – 4
- ✓ No. of Pots – 1322
- ✓ Pot Amperage – 340 KA
- ✓ Design Capacity – 1250 KTPA

- ✓ GAP – 2 Paste Plants (Outotec GMBH, Germany)
- ✓ Bake Oven – 6 Bake Furnaces
- ✓ Anode Rodding Plant

- ✓ Ingot Casting Mill – 4 Lines
- ✓ Wire Rod Mill – 2 Lines
- ✓ Billet Casting Mill – 3 Line
- ✓ Cast Bar Mill – 2 Lines
- ✓ SOW Cast – 1 Line



# PROCESS FLOW DIAGRAM





	Electrical Energy Million kWh	Thermal Energy Million kCal	Production (Hot Metal) MT
<b>FY 2019-20</b>	11741.085	212714.15	803456
<b>FY 2020-21</b>	12681.923	247870.31	871591
<b>FY 2021-22</b>	16258.724	309057.571	1142469


## Energy Sources:

- Electrical Energy: CPP, Grid
- Thermal Energy: HFO, Propane












S.No	Title of project	Annual Electrical saving (Million kWh)	Annual Thermal saving (Million kCal)	Investment (Rs in Million)
1	Replacement of Non ES pots by 100% graphatised cathodes	183.944	0	3640
2	Replacing conventional lights with LED lights	1.315	0	5.39
3	FTP-3,4 By pass duct replacement to stop draft loss	0.999	0	6.00
4	Elimination of Hot Well Pump	0.288	0	1.0
5	Overhauling of 22 kw GUG-5,6 HPP Motor	0.211	0	0.05
6	Installation of VFD in Shot Blast Turbine Motor	0.180	0	1.50
7	Old BR/CR motor to be replaced with IE3 motor	0.114	0	0.472
8	Installation of VFD in Cold Well Pumps	0.132	0	4.00
9	2nos VFD installation in Cooling ramp	0.023	0	1.60

**Total 15 EnCon projects are planned in FY23 with and investment of 3660 Million INR.**


**Total Electrical energy savings = 187.206 Million kWh**

Year	No of Energy Saving Projects	Investments (INR Million)	Electrical Savings (Million kWh)	Thermal Savings (Million kCal)	Savings (INR Million)
FY 2019-20	17	1733.746	36.529	37.5	125.789
FY 2020-21	17	3844.45	43.589	1257.3	112.32
FY 2021-22	19	5345.99	316.149	0	1210.87

A total of 53 Energy saving projects are being implemented in last three years with a total investment of 10924 Million INR.



Target is to complete Graphatised cathode implementation in 100% Pots by FY25





Continuous investment done in replacement of conventional lights to LED.

Procurement of spares for conventional lights is stopped

## ELIMINATION OF IDLE RUNNING OF EQUIPMENTS


- R&T Group of GAP: Both R & T group used to run the entire time regard less whether the downstream equipment not operational. PLC logic is implementer in R & T group if downstream equipment is not running for 30mins due to any plant breakdown or maintenance job they will automatically stop
- Coke conveying belt of GAP: Load cell is installed for coke conveying belt 101A, On an average running hours of conveyor reduced by 1hr.
- Bakeoven: Idle running of HPP, RB-14 conveyor in grouping CC-2, RB-25 conveyor in ungrouping CC\_2 is eliminated by implementing logic in PLCs.





**PLC logic of RB-14 conveyor**

This resulted an annual saving of 170 MWH in FY22

SI No	Year	Type of waste generated	Quantity of waste generated (MT/year)	Disposal Method
1	2019-20	Spent Pot lining	19802.41	Disposed through State PCB authorised agency
2	2020-21	Spent Pot lining	11212.52	
3	2021-22	Spent Pot lining	31230	



Year	Scope 1 emissions CO <sub>2</sub> e (MT)	Scope 2 emissions CO <sub>2</sub> e (MT)	Scope 3 emissions CO <sub>2</sub> e (MT)	CO <sub>2</sub> e MT
2019-20	2,28,93,187	8,02,665	3,77,712	2,40,70,583
2020-21	2,39,26,260	5,10,837	3,39,940	24,437,097
2021-22	2,38,95,350	19,56,916	50,05,928	3,08,58,194



## Long-term Action Plans for CO<sub>2</sub> emission reduction

**Reduction of 596301 T CO<sub>2</sub> emission  
by FY25 through installation of  
100% graphatised cathodes and  
process improvement**

**Reduction of 579419 T CO<sub>2</sub> emission  
by FY25 through vedanta  
potcontroller**

**Reduction of 265415 T CO<sub>2</sub> emission  
by FY23 through solar**

**GHG emissions data is publicly  
disclosed in the Vedanta group  
sustainability report**






# NATIONAL ENERGY CONSERVATION WEEK CELEBRATION



- Energy awareness campaign in plant by different internal departments
- Online quiz competition for Vedanta employee
- Awareness training for school children
- e-paper presentation for school
- Best energy conservation idea competition for contract partner,





**CII Energy Efficient Unit FY 18-19**

**CII Energy Efficient Unit FY 19-20**

**SEEM Energy Awards Gold Award  
FY 19-20**



**CII Energy Efficient Unit FY 20-21**


**We Vedanta Limited, Smelter-2, Jharsuguda have participated in 20<sup>th</sup>, 21<sup>st</sup> & 22<sup>nd</sup> National Award for Energy Excellence in Energy Management and secured Energy Efficient Unit award.**

**Got Gold Award in SEEM Energy Awards 2020.**

## ISO 50001

- Recertification done to ISO50001:2018 in FY21-22.
- All the EnCon projects are identified and have been driven by EnMS Team under ISO50001

INR 534.6 crores invested in Energy conservation projects in FY21-22, which is 2.05% of turnover.





- **100% Graphatised Cathode Implementation in 100% Pots by FY25**



- **Installation of solar power plant**



- **Use of RUC copper inserted collector bar for pot cathode.**



- **100% implementation of LED**



- **Implementation of Vedanta Pot controller**

# THANK YOU!