



■ Team Members

- Mr Abhishek Saxena, DGM EEMG
- Mr Arnav Kothiyal , Senior Manager EEMG

ISO 9001:2015,
ISO 14001:2015,
ISO 45001:2018,
ISO 50001:2018




Sipat Super Critical Boiler (2980 MW, 660 MW X 3 + 500 X 2 MW)




*1st Supercritical project of NTPC
1st 660 MW plant to install De-Nox System
FGD under Commissioning*





**MS Temp: 537 Deg C
Reheat Temp: 565 Deg C
Boiler Pressure: 273 Ksc**



Sustainability & Power




SIPAT: Consistent performer over the years



Gross & Net Heat Rate Trends



- Central electricity regulatory commission (CERC) has fixed a normative Heat Rate for NTPC Sipat at 2338 kcal/kwhr based on the technology.
- NTPC Sipat has been able to maintain Gross Heat Rate below the Norms continuously for the past few years.
- Despite low PLF Heat Rate improved by 29 Kcal/kWh (CERC allows a degradation 1.25 %/29.35 kCal/kWh).
- **Net Heat-rate improved by 29 Kcal/kWh over previous Year.**



Benchmarking

Internal NTPC Performance Evaluation Matrix Ranking

- NTPC has a system of evaluating performance of its station based on a comprehensive matrix which covers all the aspects of performance like O&M Index, MOU Index, Thrust Area Index and Fuel index.
- Business Excellence(BE) department through BE position report.

Year	2017-18	2018-19	2019-20	2020-21	2021-22
Position	5 th	1 st	4 th	1 st	4 th



APC Benchmarkng- With NTPC Mauda



SN	Description	Sipat- Stg I 660 MWX3	Mouda- Stg II 660MWX2	ECl-Sipat	ECl-Mouda (KW /MW)
		KW	KW	KW / MW	KW / MW
1	Draft Power	33501	18800	16.9	14.2
2	Milling Power	9986	7538	5.0	5.7
3	Condensate System	6772	5012	3.4	3.8
4	CW System	17404	10728	8.7	8.1
5	ESP System	5702	4510	3.0	3.4
6	Ash Handling system	5234	3380	1.75	1.60



Action plan made for improving the Draft power & In Unit 1 after AOH Draft power ECI is 12.0 kW/Kwh. Unit 2 under AOH.

CW system ECI higher due to Design

100 % Dry ash utilization.



Water Consumption Benchmarking – NTPC Mouda



- Specific water consumption : Mouda- 2.16; Sipat 2.48Lt/unit
- Only one reservoir in Mouda, capacity leading to reduced seepage and evaporation losses.
- Dry ash utilisation 100% in Mouda due to high demand.
- Action plan enforced to reduce the water loss in fire system & Service water, around 11 KM water pipe line being replaced.



Bench Marking



External : PAT (perform Achieve and Trade)



NTPC Sipat is Notified by BEE under PAT cycle VII



Baseline : 2418 kCal/kWh @ 2018-19



Target : 2412 kCal/kWh Assessment Year 2024-25.

PAT CYCLE	PERIOD	Assessment Year	NHR TARGET	NHR ACHIEVED	ESCERTS
PAT CYCLE-I	2012-15	2014-15	2484	2438	+36443
PAT CYCLE-II	2016-19	2018-19	2430	2424	+13499

NTPC SIPAT TRADED CYCLE-1 ESCERTS ON IEX AND EARNED APPX 3 Cr.

PAT CYCLE-II M&V AUDIT , AEA RECOMMENDED FOR 13499 ESCERTS





New Initiatives, Technology Use & Process Improvement Projects

In-house Application for Generation Monitoring



*Implemented in 24 NTPC Projects.
 Won NTPC Professional Circle Championship for This application

ABT Version 6.1 (WR, ER and NER) Dated: 14/2/2023

ABT / RAMP RATE MONITORING SYSTEM

Block : 86 21:15-21:30
 Time Left **13:20**

SG+AGC	AG
1802	1853

10% Dev Limit	Dev (MW)	DEV (%)
100	51.81	2.88

INST FREQ	AVG FREQ	PRED FRQ
50.00	50.011	50.00

UI within +/-10%

Original SG : 1856.3	Day Tot DSM (Rs)
90% SG : 1702	Avg AGC : -54.67 0.48 Lakh
110% SG : 1902	Instn AGC : -64.16 DAM : Rs. 7.60
Inst Gen : 1842.02	Predicted Gen : 1843 RTM : Rs. 12.00

Asking Rates :

49.95 Hz : 49.94 Hz	90% SG : 1908.03 MW	Block Net DSM : 0
50.03 Hz : 50.03 Hz	110% SG : 2133.03 MW	DSM Charges: 21888

Asking Rate For SG **1795**

RTDA Rate (P/KWh): <input type="text" value="40.34"/>	ECR : <input type="text" value="169"/>
Normative SG(MW): <input type="text" value="1856.25"/>	<input type="button" value="SAVE"/>

Fuel Cost: -21888
RTDA Charges: 0

RAMP RATE PREDICTION

Required Ramp Rate : -21 (-0.07%)
 Actual Ramp Rate : 29 (0.1%)
 Predicted Ramp Rate : 19 (0.07%)

Todays Total Ramps : 0
Ask Rate

	SG	0.5 %	1 %
SETPOINT	1801.58		
ASKING	1795		
Dev	52		

No Ramp

SYSTEM STATUS

Internet connection **Rev No**
 PI Connection **184**
 Fetching SG
 Counter : 819
 SG Fetching Time : 15/02/2023 09:13:33 PM
 System Time : 15 Feb 2023, 09:16:43 PM
 DAM : 15/02/2023 RTM : 15/02/2023

CONTROL SECTION

Start Application

 Monochromatic

Sipat, STAGE-1

Block	Original SG	SG+AGC	AG	UI (%)	Avg Fre
84	1856.25	1797.03	1804.89	0.4	50.0
85	1856.25	1822.18	1824.66	0.1	49.9
86	1856.25	1801.58	1853.39	2.9	50.0
87	1856.25				
88	1856.25				
89	1856.25				
90	1856.25				
91	1856.25				

Next Block Schedule

Block No	Block SG	Ramp Rate
87	1856	No Ramp

LOAD AND AGC


Unit No	Unit1	Unit2	Unit3	Tot(Nor)
Load	643	646	646	
Instn AGC	-23	-23	-23	-68.4(-64.2)
Avg AGC	-20	-19	-19	-58.3(-54.7)

Application initialized and ready to use

LAST ALERT AND SYSTEM LOGS

15/02/2023 09:15:25 PM: Error in Fetching SG got resolved
 15/02/2023 09:15:20 PM: SG Updating
 15/02/2023 09:15:20 PM: PI connection ok
 15/02/2023 09:15:15 PM: Voice Alert : Application initialized and ready to use
 15/02/2023 09:15:07 PM: Connected to PI Server
 15/02/2023 09:15:03 PM: Internet connection Restored
 15/02/2023 09:15:03 PM: Error in Fetching SG

Tending & Prediction for Correct Operation



3. REAL TIME TRENDS

1. REAL TIME VISUAL SUMMARY FULL DAY DSM REPORT

2. X-Y PLOT

Upgraded Energy Management System With Mobile Alerts



Real time Dash Board

- Home
- Real Time
- Equipments
- Communication
- Single Line
- Electrical Health
- KPI Report

ENERGY MONITORING SYSTEM
NTPC LIMITED, SIPAT (STAGE-I&II)

UTILITY SYSTEM NTPC Sipat Auxiliary Power (KW) Dashboard



Description	Unit 1	Unit 2	Unit 3	Stage-1	Unit 4	Unit 5	Stage-2	STN
UNIT APC	27,294	0	30,324	57,618	20,044	22,444	42,488	100,107
Draft Power	9,019	0	12,026	21,044	7,517	7,979	15,496	36,540
Mill Power	3,066	0	3,117	6,183	2,228	2,346	4,574	10,757
Condensate	2,227	0	2,301	4,529	1,376	1,539	2,915	7,444
CW SYSTEM	5,774	0	5,796	11,569	4,188	4,280	8,468	20,037
Cooling System	1,341	0	1,218	2,559	764	765	1,528	4,088
ESP System	1,919	234	1,982	4,134	1,560	-575	985	5,120
CT System	0	0	0	0	0	0	0	0
Feed Water	0	0	0	0	0	0	0	0
Vacuum Pump	208	0	206	414	99	98	197	610
UST	1,363	277	1,256	2,896	1,315	1,237	2,552	5,448
FGD system	0	0	0	0	0	0	0	0
Other System	12	0	179	191	530	504	1,034	1,224

Common System	Stage-1	Stage-2
Ash Handling	546	3,075
Coal Handling	1,701	483
DM Plant	375	326
Compressed Air	1,428	1,093
Fire Water	0	0
FOPH	0	0
Workshop	0	0
AWRS	0	0
ADM Building	0	0
Service Building	-63	0
Ash Silo	-3	0
RWPH	315	0
Total	9,273	0
Colony	0	0


Energy Management System – Developed By Schneider Electric

Day Report System Wise

24-Jul-2023	Today				Prev Day				Remark
Description	UNIT 1	UNIT 2	UNIT 3	Stage-1	UNIT 1	UNIT 2	UNIT 3	Stage-1	
1 APC	0.00	4.70	4.57	4.64	0.00	4.69	4.62	4.64	
2 UNIT APC	0	30538	29605	60144	0	30713	29893	60605	
3 Draft Power	0	11425	11260	22635	0	11436	11529	23025	
4 Mill Power	2	3281	3121	6415	0	3283	3190	6574	
5 Condensate	0	2359	2267	4626	0	2365	2282	4647	
6 CW Power	5797	5850	5807	11754	5797	5848	5803	11748	
7 Cooling Power	885	1405	1315	3605	1023	1405	1317	3750	
8 ESP Power	600	2208	2048	4856	596	2172	2036	4803	
9 CT Power	0	0	0	0	0	0	0	0	
10 Feed Water	0	0	0	0	0	0	0	0	
11 Vacuum Pump	0	102	104	206	0	102	104	206	
12 FGD Power	0	0	0	0	0	0	0	0	
13 UST Power	490	1249	1154	2894	450	1249	1156	2855	
14 Other	0	103	99	202	0	103	125	237	
Total	7775	27982	27186	62943	7871	28112	27562	63544	



Power trends



Pi Alert sample message

16:00 4G

QP-NTPCPI

Pi Alert Message: UNIT 3 COAL FLOW LESS THAN 430 TPH AND MORE THAN 6 MILLS ARE IN SERVICE at 9/7/2023 12:07:46 PM.Alert Evaluated at 9/7/2023 12:07:46 PM and configured by : (101859)-NTPC


13:09

Pi Alert Message: UNIT 3 COAL FLOW LESS THAN 430 TPH AND MORE THAN 6 MILLS ARE IN SERVICE at 9/7/2023 1:08:58 PM.Alert Evaluated at 9/7/2023 1:08:58 PM and configured by : (101859)-NTPC

14:09



Draft Power Improvement



Draft power reduction by duct repair, thickness mapping, NMEJ repair, **Refractory lining on flue gas guide vanes & area prone to erosion.**



Condenser Performance Improvement

- High pressure Jet cleaning done at 700-800Kg/cm² in Unit 1.
- Jet cleaning followed by bullet cleaning done in Unit 1.
- Continuous monitoring done by boroscopy to repeat jetting if dirty tube persists. **New**


The condenser vacuum in unit 1 improved more than design. Vacuum in U1, 73mmHg against a design of 77mmHg.




Environment Management

- Capturing rainwater through ZLD setup. **New**
- Water Consumption Monitoring in Real time through Water dash board
- DAES implemented in Stage I units also. Station now has 100% DAES **New**
- Rail loading of railway rakes and dispatch of Ash to Cement Industries Started. **New**
- Arresting reservoir seepage by HDPE Liner replacement. **New**
- Wet System – Stringent monitoring of Ash to Water Ratio in Daily Planning meeting , FAHP running hour optimized. **New**
- CW Cycle of Concentration (COC) has been Improved from 4 to 7 with Lot of Modification and system improvement.


Sp Water Cons. – Litre/ KWh





Water Dashboard:
Real time monitoring of water consumption.
This dashboard is selected for PAN NTPC implementation





RAINWATER HARVESTING


Water Harvested	Cost saving
1196056 m ³	146.51 Lakhs



Area	Remarks	PR Details
Plant	Facility created	<ul style="list-style-type: none"> ➤ RWH implemented on 28.8.22, near CT 2B ➤ RWH implemented on 08.10.22, near CT 1B ➤ RWH implemented on 24.12.22 near CT 3B ➤ RWH implemented on 05.06.23 near OAC 1
Hospital	Facility completed.	
Township	PO awarded	Work in progress
All area	RWH potential study by third party.	Study completed, Under Award for work





RESERVOIR 1B SEEPAGE REPAIR WORK



Total Reservoir Capacity	: 4.8 MCM.
Saving potential	: 4 MCM year
Water Cost saving	: Rs 4.6 Cr
Pumping power Saving	: 2.27 MU's / Rs 45 Lac per year
Total Cost of works	: Rs 27 Cr
Completion date	: 31.10.2023.



Environment Management: Ash Utilization



- **Modes of Ash utilization**

- Dry Ash: All units DAES commissioned
- Wet Ash

- **Distribution of areas of Ash utilization**

- Roads and Highways
- Low lying area development
- Cement Manufacturers / Bricks & Blocks
- Total Ash brick plant capacity increase to 2.5 Lac/per day with addition of 2 LPD ash brick plant. **New**
- Rail loading facility also developed and dispatch started. **New**
- Mine filling Started **New**
- Brick Dealership given to one agency. **New**
- BIS certification awarded for ash brick **New**
- Local Builder's Customer meet done to encourage use of Ash products **New**



Dry Ash Dispatch to Ultratech Cement, Aditya Nagar, Karnataka



Ash products- Displayed in exhibition




NTPC SIPAT LWA PROJECT

Fly ash based LWA Facility







Trial run started by Director – Projects



Light Weight Aggregate (LWA) plant Sipat

- Fly ash based Light weight aggregate as an alternate for natural stone concrete
- 50000 Ton capacity/year plant under commissioning, first lot to be produced by 30.09.23
- Cost of LWA Rs.1700/Ton
- Cost of Natural Stone aggregate: Rs. 2000 / Ton
- Trial run started

S N	Project	Salient features	Status
1.	Geopolymer Lab Set up <ul style="list-style-type: none"> 20 TPD equipment Testing facilities 	<ul style="list-style-type: none"> In-House Production & Testing of Ash based products Development of Design Mix for new products and on going projects 	<ul style="list-style-type: none"> Infrastructure set-up completed 20 TPD machine installed and commissioned GPCA produced Testing of GPCA under progress Water absorption - <18%, Impact /Abrasion value-<40%, etc
2.	GPCA 	<ul style="list-style-type: none"> In house development of GPCA (Geo Polymer Coarse Aggregate) Substitute for Natural resources Huge potential for bulk ash utilization (80%) 	<p>The Projects are done to establish the techno commercial viabilities of the technology. The alternate use of Ash in making aggerate and sand will make save natural resources and will result in resolving ash disposal issue.</p>
3.	NACA 	<ul style="list-style-type: none"> In house development of NACA (NANO Concrete Aggregate) Substitute for Natural resources Potential for bulk ash utilization (70%) 	

SN	Project	Project/Benefit	Status
4.	Ash to Sand	<ul style="list-style-type: none"> • Bulk ash utilization • Conservation of natural resources • Revenue Generation 	<ul style="list-style-type: none"> • Under implementation • Commissioning :March' 24
5.	Interlocking Wall Blocks 	<ul style="list-style-type: none"> • No need of plastering and mortar • Geopolymer/high volume fly ash based cement blocks possible 	



12000 Interlocking paver blocks used in Sipat



Ash to Sand Facility at NTPC Sipat



NEW ASH PROJECTS – RECENT DEVELOPMENTS



**ASH
TO
CASH**



NACA



PAVER BLOCKS



TETRA POD



SOLAR MMS PILES



LWA



GPC ROAD -ASH DYKE

GPC Road Ash Dyke-1
22-May-2023 15:32:40



HUME PIPE



BOTTOM ASH



Ash Dyke Block Mould



SOLAR MMS



Biomass Cofiring

- NTPC Sipat Started Biomass (pellet) Cofiring in FY 2022-23.
- Total Biomass cofired till date : 3444 MT
- Green Power Generated : 4.67 MU's
- CO2 generation averted : 4767 MT
- Helping Beneficiaries to meet RPO Obligations



Pellet making machine

Pelletization of Biomass generated in plant premises – to cofire with coal (200 kg/hr)



TREE PLANTATION



Tree Plantation Since Inception : 1170801

Miyawaki Technique

✓ Growing dense forest in limited space

Plant Growth in 4 Months



Mission 1 Lakh Trees in FY 2023-24



Miyawaki plantation at DM Plant



Miyawaki plantation at DM Plant

Tree plantation Plan in FY 2023-24		
1.	MGR Track (completed)	25,000
2.	DM Plant (Miyawaki) Completed	23,000
3.	Bhildi Village (Miyawaki) In progress	32,000
4.	Uchbhati village (Miyawaki) PO placed	32,000
Total		1,12,000



800 KW ROOF TOP SOLAR PV AT NTPC SIPAT



Type	Location	Installed Capacity
Rooftop Solar PV	NTPC Sipat Hospital	50 KW
Rooftop Solar PV	Administrative Building	100 KW
Rooftop Solar PV	Solar PV at various building inside the plant	650 KW



Upcoming Solar PV in Sipat:

- 200 KW Solar for Township power consumption awarded.
- 25 MW Floating solar in reservoir area
- 2MW ground mounted solar in switchyard area planned.

- Energy savings of approximately ~1.4 MU's annually.
- Environment protection by reduction carbon footprints. (12 Lakh kg CO2 avoided)




Environment Management: Emission

Particulars	UOM	2020-21	2021-22	2022-23
Total CO2 emissions	Ton/MWh	0.85	0.85	0.85
Current Sox emission at Full Load	Mg/Nm3	1029	1018	1018
Current NOx emission at Full Load	Mg/Nm3	210	140	138
Particulate matter	Mg/Nm3	35	35	32
Mercury	Mg/Nm3	0.0010	0.0010	0.0010



- ZLD compliant Station (both plant & Ash Dyke)
- FGD implementation:
Commissioning - Stage 1: FY23-24
Stage 2: FY24-25
- De NOX through combustion optimization: 100%
- Wagon Covering: All wagons are being covered with tarpaulin.
- Waste Management: Hazardous, Biodegradable, e-waste and mill Reject all are 100% disposed.
- Water Spray system strengthen in all dykes to avoid any fugitive dust emission specially during summer.



Energy Management System and SEC monitoring tools



- NTPC Sipat certified with ISO 50001:2018 certification for conformance to energy management system standards in all aspects.



Energy Savings projects implemented in last 3 years

S. No	Year	Nos of Energy Saving Projects	Investment (INR Millions)	Electrical Saving (Million kWh)	Thermal Saving (Million Kcal)	Total Saving (INR Million)
1	2020-21	11	46.5	25.3	80850	82.13
2	2021-22	7	114.78	13.64	158400	109.17
3	2022-23	5	63.0	15.94	167556	134.1

Highlight of FY 2022-23

- Repair/ Overhauling of identified mills with higher specific energy consumption
- Air ingress in duct and boiler attended during Unit overhaul
- Optimising FAHP Pump running hours.
- Stage-1 & 2 CT Fill replacement.
- Condenser water box cleaning



Teamwork Employee involvement & Monitoring

Daily Monitoring System :

- **Daily Planning Meeting(DPM)** is conducted to discuss the critical issues and previous day performance.

Review meeting :

- **Head of Plant(HOP): Safety / Environment/ Performance/ Commercial**
- **Operation Review Team (ORT): Head of Region review**
- **Regional Operation Performance Review (ROPR): Director Operation level review**
- **Management Committee Meeting (MCM) : Chairman Level Review**

Training :

- **Executive MBA (PGDBM Energy- NSB/IIM-A), Samarth Program, Executive Trainee(ET) Training- 9months**
- **All executives given 7 day mandatory training**
- **Learning from NTPC trips recommendations.**
- **Participants for BEE energy auditor / BOE / Business excellence exam.**

Audit :

- **Safety audit**
- **3 Energy audit every year.**
- **LMI audit (Internal/External/ Third Party)**
- **Technical Audit**



Learning from the CII event

- Training to O&M staff on Flexibilization by EPRI-CII expert, Knowledge shared was helpful in efficient adherence to flexible scheduling.





thank you

