

WELCOME TO




RAIN CEMENTS LIMITED

*National Award for
"Excellence in Energy Management 2024"*


RAIN CEMENTS LIMITED

UNIT-II, SREEPURAM

RAIN INDUSTRIES LIMITED (RAIN)



RAIN INDUSTRIES LIMITED (RAIN)



North America

- 7 Carbon Facilities (Including 3 River Terminals and 4 Waste-heat recovery facilities)
- 1 Chemical Facility

Europe

- 3 Carbon Facilities
- 4th Carbon Facility in Russia
- 3 Chemical Facilities

Africa

- 1 Carbon Facility in Egypt


Asia

- 1 Carbon Facility (including 1 Waste-heat recovery facility) in India
- 2 Cement Facilities in Andhra Pradesh and Telangana

Manufacturing Facilities in 7 Countries

1. Calcined Petroleum Coke : 2.4 MTPA
2. Cement : 6.57 MTPA
3. Tar Distillation : 1.50 MTPA

RCL GREEN VISION



RCL CEMENT BUSINESS



RCL Cement Business

Location	Capacity- MTPA
Ramapuram- Telangana	1.50
Sreepuram- AP	2.77
Ramapuram - Telangana (Under Execution)	2.30
TOTAL CEMENT PRODUCTION CAPACITY	6.57

Contributing to Bharath Nirman




MAJOR EQUIPMENT – RCL UNIT-II

Equipment	Supplier	Rated	Operating	Beyond Capacity
Crusher	L&T	800 TPH	920 TPH	+15%
Raw mill VRM	FLS	305 TPH	340 TPH	+11.5%
Pyro 5stage Preheater	FLS	3800 TPD	4450 TPD	+17.1%
Coal mill VRM	FLS	30 TPH	35 TPH	+16.5%
Cement mill Roller press	TKIL	145 TPH	195 TPH	+34%



FORMATION OF RCL ENERGY MANAGEMENT CELL



Designation	Roles & Responsibilities
Advisor – Tech & Head - Operations	<ul style="list-style-type: none"> • Drive the energy saving culture in the organization. • Set targets for reduction in various parameters inline with the Vision & Energy policy. • Fiscal validation of Power saving projects and necessary allocation.
Plant Head	<ul style="list-style-type: none"> • Review status of Power saving projects through Monthly review meetings. • Drive employee involvement initiatives
Department Heads & Energy Manager	<ul style="list-style-type: none"> • Identification & implementation of energy conservation projects. • Drive employee involvement initiatives. • Generate energy conservation ideas. • Measure, Monitor & analyze section wise energy consumption in the factory

RAIN CEMENTS LIMITED (RAIN)

Energy Saving Projects Implemented during 2021-2022

Sr.No	Name of Energy saving projects	Investments (INR Million)	Electrical savings (Million kWh)	Thermal savings (Million Kcal)	Total Savings (INR Million)
1	Application of Aluminum Heat resistant paint for Kiln Shell for 40 mts	0.596	0.00	22.235	3.73
2	Preheater False air reduction	0	0.06	---	0.38
3	Raw Mill False air reduction	0	0.06	---	0.35
4	Coal Mill False air reduction	0	0.07	---	0.39
5	Installation of VFD for Line-2 Blending silo aeration blower	0.25	0.06	---	0.38
6	Replacement of Line-2 Kiln shell cooling fans (metal fans) with FRP fan blades	0.1	0.20	---	1.18
7	Optimization of cooler fans operation with PID controls	0.2	0.56	---	3.37
8	Packer's hopper aeration line changed from compressed air to blower air	0.3	0.09	---	0.53
9	Installation of VFD for Line-2 LS hoppers bag filter fan	0.4	0.06	---	0.38
10	Replacement of Line-2 plant return water pump (15KW) with energy efficient pump (5.5KW)	0.5	0.10	---	0.58
11	Line-1 cementmill upgradation by installing roller press	46.9	5.29	---	31.72
12	Air conditioners switched OFF by providing heat vent-out ducting for ESP TR-set panels	0.6	0.03	---	0.18
13	Air dryer ON/OFF interlocked with compressor air line pressure	0.7	0.01	---	0.07
14	Installation of VFD for WHR Aux-cooling tower water pump	0.7	0.07	---	0.44
15	LS hoppers reversable belt conveyor removed, by arranging direct chute.	0.7	0.02	---	0.10
Total:		51.95	6.67		43.78

RAIN CEMENTS LIMITED (RAIN)

Energy Saving Projects Implemented during 2022-2023

Sr.No	Name of Energy saving projects	Investments (INR Million)	Electrical savings (Million kWh)	Thermal savings (Million Kcal)	Total Savings (INR Million)
1	Installation of 500KVAR HT Capacitor bank at Line-2 load center-4 to save energy by improving power factor.	0.36	0.35	--	1.93
2	Plant water pump (U2CH800-15KW) replaced with energy efficient pump (5.5KW)	0.11	0.09	--	0.52
3	Line-2 Raw Mill Main drive power reduced by increasing mill temperature increased 65°C to 72°C	0.00	0.36	--	2.19
4	Line-2 Raw mill auxiliary Bag filters purging time increased from 12 sec to 30 sec	0.00	0.05	--	0.33
5	Installation of compressor air flow meters phase-II	0.67	0.10	--	0.58
6	Replacement of Line-1 DC motors with AC Motors	0.15	0.02	--	0.10
7	Replacement of Line-2 water feeding standby pumps (45KW & 22KW) with energy efficient pump (45KW)	0.15	0.15	--	0.90
8	Installation of roof top solar 40KW on canteen and 20KW on Administrative building	2.03	0.08	--	0.50
9	Optimize the Ventilation volume of packing plant bag filter fans for all 3nos by installing VFDs	0.66	0.23	--	1.37
10	Optimization of compressor pressure settings to save energy	0.00	0.35	--	2.09
11	Optimization of transformers operation	0.00	0.04	--	0.27
12	Installation of additional cooler for Line-2 Cement mill Slide shoe bearing	0.40	0.05	--	0.28
Total:		4.53	1.87	--	11.04

RAIN CEMENTS LIMITED (RAIN)

Energy Saving Projects Implemented during 2023-2024

Sr.No	Name of Energy saving projects	Investments (INR Million)	Electrical savings (Million kWh)	Thermal savings (Million Kcal)	Total Savings (INR Million)
1	Avoid pressure drop & damper Loss in Auxiliary bag filter fans (3Nos) in Line-2 VRM by providing VFDs.	1.13	0.19	---	1.05
2	Lightly loaded Motors connections conversion from Delta to Star in Line-1 Polycom, Packer & L2 VRM.	0.00	0.05	---	0.26
3	Optimization of air conditioner's operation in Line1 Polycom & Line-2 LC-1.	0.00	0.03	---	0.17
4	Line-1 Polycom belt (5C1-BCO4) Removed by arranging Y-chute.	0.18	0.05	---	0.27
5	Line-1 Cement mill CA fan HT Motor (350KW, 6.6KV) replaced with LT Motor (160KW) with VFD	0.18	0.24	---	0.86
6	Line-1 Polycom Baghouse fan Soaft Starter replaced with VFD.	1.05	0.57	---	3.12
7	Replacement of Line-2 cement mill recirculation water pump with energy efficient pumps	0.15	0.03	---	0.19
8	Replacement of Single stage centrifugal pump (15KW) with multistage submersible pump (7.5KW) for Line-2 make up water pump.	0.04	0.07	---	0.36
9	under rating roots blowers with suitable blower for Fly ash unloading at Line-2 Cement mill	0.35	0.04	---	0.22
10	Optimization of Line-2 RABH pursing time to save energy	0.00	0.98	---	5.38
11	Usage of tyre oil in place of HSD for Kiln's light up firing	1.08	0.00	229.77	10.34
12	Utilization of Lime stone in place of Fly ash as performance improver	0.00	0.00	---	24.33
13	Line-2 Cooling tower Fans start-stop logic for running hours optimization	0.02	0.03	---	0.14
14	Optimization of Compressor air in Line-2 Kiln & coal mill sections	0.00	0.37	---	2.02
15	Coal crusher bypass during coal crushing	0.00	0.25	---	1.35
Total:		4.17	2.88	229.77	50.07


RAIN CEMENTS LIMITED (RAIN)

Energy Saving Projects Planned during 2024-2025


Sr.No	Title of Project	Annual Electrical Saving (Million kWh)	Annual Thermal Saving (Million Kcal)	Annual Energy Saving (ToE)	Investment (Rs in Million)	Estimated Payback (months)
1	Installation of Energy Savers for AC units	0.30	0	25.800	1.096	7.43
2	Reduce preheater and kiln radiation losses by thermal insulation paint-Phase-2	0.00	4137.536	413.754	1.166	2.06
3	SPRS for Line-2 VRM CA Fan	1.88	0	161.353	20	23.26
4	Installation of 883 KVAR HT capacitor bank to improve power factor.	0.14	0	12.37	0.648	8.33
5	Line-2 Cooler upgradation to increase recuperation efficiency	0.00	7341.477	734.148	27.5	27.42
6	L2 Cooler out bag filter fan switched off by connecting venting line to ESP fan	0.09	0	8.037	0.2	4.35
7	Installation of Efficient blower for Kiln Firing	0.144	1.3392	12.384	10	52.17
8	Replacement of Line-2 Cement mill CA Fan with energy Efficient impeller	0.792	0	68.112	8	22.04
9	Harmonic study in all load centers and installation of Harmonic filters	0.11	0	9.382	0.3	6.00
10	Operating CEP to maintain the Deaerator level by VFD control rather than control valve	0.09	0	7.818	0.85	20.40
11	Installation of solar water heaters for colony Quarters (A+, A, B,C,D,E, F & SR)	0.20148	0	17.327	8.98	89.17
12	Installation of roof top solar power on Mines office, school & Hospital	0.1914	0	16.460	3.721308	38.89
13	Construction of New CSP in Line-2	0	145.879	1.646	2538	20.15

SUMMARY OF PROJECTS IMPLEMENTED IN LAST 3 YEARS


Projects implemented in last 3 years



Electrical savings (Million kWh)



Thermal savings (Million Kcal)



Year	Reduction SEC kWh /MT cement
2021-22	3.61
2022-23	0.94
2023-24	1.36

ENERGY CONSUMPTION - CLINKER


Specific power consumption

Up to Clinker – KWh/T



Specific Heat Consumption

Kcal/Kg Clinker




ENERGY CONSUMPTION IN 2022-23 INCREASED DUE TO USAGE OF PET COKE

ENERGY CONSUMPTION - CEMENT


Specific power consumption

Up to OPC – KWh/T



Specific Power Consumption


Up to PPC – KWh/T



ENERGY CONSUMPTION IN 2022-23 INCREASED DUE TO USAGE OF PET COKE

ENERGY CONSUMPTION – TOP TEN CEMENT PLANTS

Overall SEC & Clinker factor




Innovative Project – 1 : Additives Mixing in Limestone Pile



ADVANTAGE: *ZERO INVESTMENT*

- **Uniform Quality of Raw Mix**
- **Smooth Operation of Kiln**
- **Avoided internal movement of Additives**
- **Stopped Additive Crusher**
- **Reduction in HSD Consumption**
- **No Jamming in Chutes / Hoppers**
- **Consistence in Quality of Clinker**
- **Reduction in Clinker Cost**
- **Reduction in CO2 Emission due to less HSD Consumption**

Innovative Project – 2 : Enhancement of PPC Production



Project Description:

Previously in Line-1 cement mill Gypsum weigh feeder capacity was 15 Tons only, due to this, we are unable to increase cement mill production.

Action Taken:

Our team decided to modify the gypsum weigh feeder chute by extra opening and adjusted the load cells up to 22 tons capacity. Test trial was taken and achieved an increased in PPC Production from 165 TPH to 195 TPH.

Benefits: ZERO INVESTMENT

PARTICULARS	BEFORE	AFTER
RP Output -TPH	165	195
Power Consumption- KWh/T	26.23	23.23
Fly Ash %	32	33

➤ Amount Saved : Rs 20.64 Lakh/Year

Innovative Project – 3 : Enhancement Limestone pile Capacity



Project Description:

- ❖ Previously limestone Pile Capacity is 18,500 MT
- ❖ Mining Equipment is being utilized under capacity

Action Taken:

- ✓ Increased the Stacker retention time at both ends of limestone pile
- ✓ Increased the Stacker boom height by 500 mm

Benefits: **ZERO INVESTMENT**


PARTICULARS	BEFORE	AFTER
Pile Capacity - MT	18,500	22,500
Reclaimer output- TPH	500	530
Reclaimer power- KWh	94	88

Innovative Project – 4 : Cement Mill CA fan HT Motor(350KW) replaced with LT Motor (160KW)

BEFORE



AFTER



Project Description:

- ❖ Previously Line-1 Cement mill CA fan 350KW 6.6KV HT motor operating @ 95KW.
- ❖ After Polycom installation, it was found under loaded, there is margin for energy saving by replacing with suitable rating LT motor

Action Taken:

- ✓ Proposed to replace 350KW HT motor with available 160KW LT Motor with VFD to save energy.

Benefits:

PARTICULARS	BEFORE	AFTER	Saving(Kw)
Power consumption(KW)	97.32	61.4	35.92

Energy Savings per annum: 1,56,710 KWH

Reduction in Specific power: 1.5kwh/ton of cement

- Amount Saved : Rs 8.61 Lakh/Year

ROAD MAP FOR ACHIEVING NATIONAL / INTERNATIONAL BENCHMARK

**TARGET TO ACHIEVED POWER
REDUCTION BY 4.50 KWh/T OF
CEMENT IN NEXT THREE YEARS**

**Installation of
IFC Controller for
Air Compressors**

**Installation of
VFD for WHR
CEP pump**

**Installation of
Energy Savers
for AC units**

**Cooler ID
fan Retrofit**

**Energy Efficient
Air Compressors
for packing plant**

ROAD MAP FOR ACHIEVING NATIONAL / INTERNATIONAL BENCHMARK

**TARGET TO ACHIEVED SPECIFIC HEAT
REDUCTION BY 20 Kcal/Kg CLINKER
IN NEXT THREE YEARS**

Reduce preheater
and kiln radiation
losses by thermal
insulation paint-
Phase-2

Reduction of
False Air save 2
kcal by Sep'2024

Process
Optimizer Expert
System
(Fuzzy logic)

Cooler
upgradation to
increase
recuperation
efficiency

RCL RENEWABLE ENERGY



RAIN CEMENTS LIMITED

RCL GREEN POWER

Green Power	Capacity
Solar	19.30 MW
WHR	10.60 MW
Total	29.90 MW

Contributing to 43% RCL Power Requirement

RCL UNIT-2 SOLAR POWER PLANT

CAPACITY : 13.26 MW

Our Plant is operating with 43% of Green Energy

RAIN CEMENTS LIMITED

RCL CEMENT UNIT - II

Transforming
Waste Heat
into Electricity.



Waste Heat



Recovery
System



Electricity

**INSTALLED 6.45 MW
WHR PLANT
CATERING TO 32%
OF OUR POWER
REQUIREMENT**



*Established **RAIN** Oxygen park with 8,200 Saplings as a part of Environmental Sustainability.*




RAIN CEMENTS LIMITED



WE ARE MORE THAN FOUR TIMES WATER POSITIVE



Our Conservation efforts helped us Harvest 10,234 Million Liters Rainwater within our Premises and nearby Villages, boosting Water availability for local Communities around our Plant.





Waste utilization and management



Waste as fuel	2021-22 (MT)	2022-23 (MT)	2023-24 (MT)
Waste grease	23	19	38
Waste Oil	8	12	59
PP bags wrapper	1548	1674	2479
Plastic waste	10	13	39

RAIN GHG JOURNEY

Scope -1,2& 3 emission Kg CO₂ / T Cement Journey



RCL Achievements – Green Supply Chain

- **Adopted *Green Transport Policy* for transportation of cement and enforcement of *Green Procurement Policy* for selection of suppliers to purchase critical equipment**
- **Relocation of bag / raw material suppliers to closer proximity of cement plant to minimize transportation**
- **Provided housing facility for 95% of employees within one KM radius**
- **Streamlining movement of vehicles inside the factory**
- **Installed RFID in the vehicles to improve vehicle turn around time**
- **Implemented Reverse logistics for cement and coal / additives transport**
- **EVs have been used for internal transportation.**

RCL – Net Zero Commitment



1

Road map for achieving target

- Installed 13.26MW solar power plant (onsite).
- Further Purchase Green Power 50 lakhs units per year.

2

Short term action plan

- Plantation 50000 saplings per year
- Increase Blended cement (PPC).

3

Long-term action plan

- Reduction of Scope-1 by enhancing AFR up to 30% TSR by 2030
- Conversion of Mines vehicles into E-vehicles.

RAIN CEMENTS LIMITED
RCL CEMENT UNIT - II

RCL BEST PRACTICES

COLLECTION AND FIRING OF COLONY WASTE





DEDUSTING STATION FOR EMPLOYEES & WORKMEN

To meet OSHA Standards, RCL installed this Blower to give safe and effective tool for dedusting and clean down of their Employees work wear and PPE equipment

- ❖ **THIS BLOWER PRODUCES HIGH VOLUME AND LOW PRESSURE AIR WHICH POSES NO THREAT TO PERSONAL SAFETY**
- ❖ **LOWER NOISE EMISSIONS (< 78dB)**
- ❖ **LOW POWER CONSUMPTION**

GOSALA – RCL CEMENT PLANT



RCL Gosala main aim is to Provide Shelter and good food to Cows collected from local villages

SOLAR – RCL CEMENT PLANT



COLONY RESIDENTIAL COMPLEXES COVERED WITH SOLAR WATER HEATERS / STREET LIGHTS / SOLAR FENCING

Equipment condition monitoring by Thermography

Line-1 Raw mill fan motor

Company: Rain Cements Limited
Unit 2 Sreepuram Nandyal(Dist)
Tester: G Bhaskar Reddy


Customer: Line-1 Raw mill fan motor
Unit-2 Sreepuram Nandyal

Device: testo 875-1i
Serial No.: 2562953
Lens: 32° x 23°

Task: Thermography of Line-1 Raw mill fan motor

Picture data: Date: 12/22/2023, Time: 2:02:14 PM, File: IV_00990.BMT
Emissivity: 0.95, Refl. temp. [°C]: 20.0

Measurement Objects	Temp. [°C]	Emiss.	Refl. temp. [°C]	Remarks
Measure point 1	53.7	0.95	20.0	-
Measure point 2	42.7	0.95	20.0	-



Remarks: Non drive end side bearing temperature analyzed by thermography instrument found satisfactory.

Review: Raw mill fan motor bearings and slip ring unit jumpers connection area temperatures analyzed by thermography instrument found satisfactory.

Compressor air monitoring through air flow meters on daily basis



Date	L-2 LS Crusher (m3)	L-2 LS Crusher RHS	Air Per hour	Production	Per ton Material	L-2 Coal Crusher (m3)	L-2 Coal Crusher RHS	Air Per hour	Production	Per ton Material	L-1 Crusher (m3)	L-1 Crusher RHS	Air Per hour	Production	Per ton Material	L-2 Rawmill hoppers (m3)	L2 Rawmill (m3)	L2 (F+G) Rawmill total	Raw mill RHS	Air Per hour	Production	Per ton Material
01.04.2024	84	13.400	6.27	10379	0.008	399	17.166	23.24	459.000	0.87	53	0.000	#DIV/0!	0.000	#DIV/0!	690	1055	1745	24.00	73	7494.10	0.23
02.04.2024	26	10.700	2.43	8024	0.003	423	16.333	25.90	455.000	0.93	51	0.000	#DIV/0!	0.000	#DIV/0!	656	858	1514	24.00	63	7574.60	0.20
03.04.2024	29	11.667	2.49	8553	0.003	398	15.583	25.54	424.000	0.94	65	0.000	#DIV/0!	0.000	#DIV/0!	676	860	1536	22.67	68	7127.80	0.22
04.04.2024	0	2.200	0.00	1653	0.000	191	16.417	11.63	457.000	0.42	61	0.000	#DIV/0!	0.000	#DIV/0!	509	953	1462	16.17	90	5089.60	0.29
05.04.2024	27	11.800	2.29	9084	0.003	310	16.500	18.79	448.000	0.69	106	0.000	#DIV/0!	0.000	#DIV/0!	574	683	1257	18.25	69	5937.20	0.21
6.04.2024	31	12.000	2.58	9078	0.003	305	14.500	21.03	404.000	0.75	66	0.000	#DIV/0!	0.000	#DIV/0!	531	608	1139	15.75	72	5291.30	0.22
07.04.2024	0	0.000	#DIV/0!	0	#DIV/0!	295	17.500	16.86	485.000	0.61	63	0.000	#DIV/0!	0.000	#DIV/0!	670	804	1474	23.50	63	7884.10	0.19
08.04.2024	80	12.667	6.32	9342	0.009	357	16.583	21.53	465.000	0.77	107	0.000	#DIV/0!	0.000	#DIV/0!	572	796	1368	20.50	67	6825.80	0.20
09.04.2024	0	0.000	#DIV/0!	0	#DIV/0!	322	14.667	21.95	409.000	0.79	22	0.000	#DIV/0!	0.000	#DIV/0!	554	1428	1983	18.50	107	6202.40	0.32

Equipment Loads monitoring as per schedule with power analyzer




GreenCo Certification & LCA

CII GreenCo Rating System – Roadmap Rain Cements Ltd, Nandyal



- Implementation timeline -4 to 6 months
- Validity of the rating 3 years
- Annual Online Sustenance review



LCA REPORT

Draft report received on LCA conducted. Final report to be received



Draft LCA Results for Priya Cement– OPC, PPC

Rain Cements Limited (RCL), 9th July 2024






RAIN CEMENTS LIMITED

PAT- TARGTES & EnMS System



PAT TARGTES & ACHIEVEMENTS




Energy Management System

- Equipment wise real time energy 30KW & above and all equipment



Energy savings Certificates



Bureau Veritas Certification

ISO 5001 CERTIFICATE

RAIN CEMENTS LIMITED



RAIN CEMENTS LIMITED

SREEPURAM, BOINCHERUVUPALLI VILLAGE, PEAPULLY MANDAL, NANDYAL DISTRICT - 518 220, ANDHRA PRADESH, INDIA.

Bureau Veritas Certification Holding SAS - UK Branch certifies that the Management System of the above Organisation has been audited and found to be in accordance with the requirements of the Management System Standard detailed below.

Standard

ISO 5001:2018

Scope of certification

MANUFACTURE AND DESPATCH OF CEMENT

Original cycle start date: 07 July 2023
 Expiry date of previous cycle: Not Applicable
 Certification Audit date: 19 April 2023
 Certification cycle start date: 07 July 2023

Subject to the continued satisfactory operation of the Organisation's Management System, this certificate is valid until: 06 July 2026

Certificate No. IND.23.7570/EN/UK Version: 1 Issue date: 07 July 2023

J. Manian

For certificate authenticity, click here <https://certcheck.ukas.com/>

ISO 50001 IN043726

Signed on behalf of BVCH SAS UK Branch
Jagdeesh N. MANIAN
Director - CERTIFICATION, South Asia
Commodities, Industry & Facilities Division




Certification body address: 8th Floor, 66 Prescot Street, London, E1 6HG, United Kingdom.

Local office: Bureau Veritas (India) Private Limited (Certification Business)
72 Business Park, Marol Industrial Area, MIDC Cross Road 'C',
Andheri (East), Mumbai - 400 093, India.

Further clarifications regarding the scope of this certificate and the applicability of the management system requirements may be obtained by consulting the organisation.
To check this certificate validity please call + 81 22 8274 2000.



ENERGY CONSERVATION DAY - 14th DEC-2023





THANK YOU

WE WORK TOGETHER AS PARTNERS