



NTPC SIPAT CII Power plant Summit 2024



Follow us on:



NTPC Sipat Station - 2980 MW



First Super Critical Power Plant of NTPC



Location	• Sipat, Bilaspur
Nearest Rail head	• Bilaspur
Nearest Airport	• Bilaspur (30KM) & Raipur (155 KM)
Capacity (2980 MW)	• St-I (3 X 660 MW): 1980 MW: • St-II (2 X 500 MW): 1000 MW
Commercial Operation	St-I (1980 MW): 01 Aug'2012 St-II (1000 MW): 01 Jan'2009
Proposed Expansion	Stage-3 : 1X800 MW Ultra Super Critical




Sipat Super Critical Boiler (2980 MW, 660 MW X 3 + 500 X 2 MW)







1st Supercritical project of NTPC

1st 660 MW plant to install De-Nox System & FGD System

MS Temp : 537 Deg C
Reheat Temp : 565 Deg C
Boiler Pressure : 273 Ksc



SIPAT: Consistent performer over the years



APC is Best among all NTPC Station




Gross & Net Heat Rate Trends

CERC has fixed a normative Heat Rate for NTPC Sipat at 2338 kcal/kwhr based on the technology.

NTPC Sipat is a consistent improver of Net Heat Rate.

Despite high planned outage (10.71 %) resulting in lesser PLF Heat Rate improved by 29 Kcal/kWh.


Improvement in APC 0.13 % & Heatrate 22 Kcal/kWh.





Benchmarking with NTPC Best

APC Benchmarking- With NTPC Mauda



S N	Description	Sipat- Stg I 660 MWX3	Mouda - Stg II 660M WX2	ECI- Sipat	ECI- Mouda (KW /MW)
		KW	KW	KW / MW	KW / MW
1	Draft Power	33501	18800	16.9	14.2
2	Milling Power	9986	7538	5.0	5.7
3	Condensate System	6772	5012	3.4	3.8
4	CW System	17404	10728	8.7	8.1
5	ESP System	5702	4510	3.0	3.4



Upgraded Energy Management System With Mobile Alerts



Real time Dashboard

Home

Real Time

Equipments

Communication

Single Line

Electrical Health

KPI Report

ENERGY MONITORING SYSTEM
NTPC LIMITED, SIPAT (STAGE-I&II)

Server Reports

UTILITY SYSTEM **NTPC Sipat Auxiliary Power (KW) Dashboard**


Description	Unit 1	Unit 2	Unit 3	Stage-1	Unit 4	Unit 5	Stage-2	STN	Common System	Stage-1	Stage-2
UNIT APC	27,294	0	30,324	57,618	20,044	22,444	42,488	100,107	Ash Handling	546	3,075
Draft Power	9,019	0	12,026	21,044	7,517	7,979	15,496	36,540	Coal Handling	1,701	483
Mill Power	3,066	0	3,117	6,183	2,228	2,346	4,574	10,757	DM Plant	375	326
Condensate	2,227	0	2,301	4,529	1,376	1,539	2,915	7,444	Compressed Air	1,428	1,093
CW SYSTEM	5,774	0	5,796	11,569	4,188	4,280	8,468	20,037	Fire Water	0	0
Cooling System	1,341	0	1,218	2,559	764	765	1,528	4,088	FOPH	0	0
ESP System	1,919	234	1,982	4,134	1,560	-575	985	5,120	Workshop	0	0
CT System	0	0	0	0	0	0	0	0	AWRS	0	0
Feed Water	0	0	0	0	0	0	0	0	ADM Building	0	0
Vacuum Pump	208	0	206	414	99	98	197	610	Service Building	-63	-3
UST	1,363	277	1,256	2,896	1,315	1,237	2,552	5,448	Ash Silo	-3	0
FGD system	0	0	0	0	0	0	0	0	RWPH	315	0
Other System	12	0	179	191	530	504	1,034	1,224	Colony	0	0
Total										9,273	0

Energy Management System – Developed By Schneider Electric


Day Report System Wise

24-Jul-2023	Today				Prev Day				
Description	UNIT 1	UNIT 2	UNIT 3	Stage-1	UNIT 1	UNIT 2	UNIT 3	Stage-1	Remark
1 APC	0.00	4.70	4.57	4.64	0.00	4.69	4.62	4.64	
2 UNIT APC	0	30538	29605	60144	0	30713	29893	60605	
3 Draft Power	0	11425	11260	22635	0	11436	11529	23025	
4 Mill Power	2	3281	3121	6415	0	3283	3190	6574	
5 Condensate	0	2359	2267	4626	0	2365	2282	4647	
6 CW Power	5797	5850	5807	11754	5797	5848	5803	11748	
7 Cooling Power	885	1405	1315	3605	1023	1405	1317	3750	
8 ESP Power	600	2208	2048	4856	596	2172	2036	4803	
9 CT Power	0	0	0	0	0	0	0	0	
10 Feed Water	0	0	0	0	0	0	0	0	
11 Vacuum Pump	0	102	104	206	0	102	104	206	
12 FGD Power	0	0	0	0	0	0	0	0	
13 UST Power	490	1249	1154	2894	450	1249	1156	2855	
14 Other	0	103	99	202	0	103	125	237	
Total	7775	27982	27186	62943	7871	28112	27562	63544	


CURRENT DAY




PREV DAY




Power trends



Pi Alert sample message



Sustainable Improvement in Draft Power



Draft power reduction by duct repair, thickness mapping, NMEJ repair, **Refractory lining on flue gas guide vanes & area prone to erosion.**

Unit 1 & Unit 2 overhauling completed 8-10 months ago and draft power still maintaining at 8000KW, approx. 1300KW better than pre-overhauling level



Sustained Condenser Performance Improvement

High pressure Jet cleaning done at 700-800Kg/cm² in Unit 1.

Jet cleaning followed by bullet cleaning done in Unit 1.


Continuous monitoring done by boroscopy to repeat jetting if dirty tube persists.

The condenser vacuum in unit 1 improved more than design. Vacuum in U1, 73mmHg against a design of 77mmHg.

Sustained Heat Rate Improvement: Despite poor Cooling Tower performance in Rainy season, No heat rate loss due to vacuum



Minimising Startup Oil Consumption & Startup Power



Bench Marking



External : PAT (perform Achieve and Trade)



NTPC Sipat is Notified by BEE under PAT cycle VII



Baseline : 2418 kCal/kWh @ 2018-19




Target : 2412 kCal/kWh Assessment Year 2024-25.

PAT CYCLE	PERIOD	Assessment Year	NHR TARGET	NHR ACHIEVED	ESCERTS
PAT CYCLE-I	2012-15	2014-15	2484	2438	+36443
PAT CYCLE-II	2016-19	2018-19	2430	2424	+13499

NTPC SIPAT TRADED CYCLE-1 ESCERTS ON IEX AND EARNED APPX 3 Cr.

PAT CYCLE-II M&V AUDIT , AEA RECOMMENDED FOR 13499 ESCERTS





New Initiatives, Technology & Process Improvement Projects




IOT BASED ASH TRUCK GATE ENTRY SYSTEM For Reducing Dry Ash Dispatch Time (In house)

4:49 PM | 0.4KB/s

☰ 🔍 ↻

Today's Trip Barchart

SHRI SOURABH SAGAR RM INFRASTRUCTUF 1/4



Agency	Trips
SHRI SOURABH SAGAR	33
RM INFRASTRUCTUF	8

Today's Trucks list

Vehicle No	Validity Status	IN-Time
RJ13GC1257	Valid	4:50:49 AM
CG10BM2212	Valid	4:56:58 AM
CG10BL2083	Valid	5:00:02 AM
RJ11GB3581	Valid	5:04:08 AM
CG10BL2095	Valid	5:09:28 AM
RJ11GB8179	Valid	5:15:40 AM
RJ11GC1339	Valid	5:16:28 AM

Yesterday Trips |
 Today's Trip |
 IN-SCAN |
 OUT-REPORT |
 SCAN SUMMARY |
 Daily Trips



PC and Printer for CISF for viewing and Printing reports



Real Time Dashboard (Android, Apple, Windows)



ASH TRUCK ENTERY

Search REPORT SUMMARY




REPORT SUMMARY

SUMMARY

Description	Data
12/27/2023	
Total Truck Trips	44
Total Truck Inside Plant	24
12/26/2023	
Total Truck Trips	50
Total Truck Inside Plant	0


Todays Trip Barchart




Agency Wise Trips

Agency	Todays Trips	Yesterdays Trip	Day before Yest
SHRI SOURABH SAGAR	34	50	69
RM INFRASTRUCTURES	0	0	1
OM SHARDA LOGISTICS	0	0	0
REFEX LTD	0	0	0
OTHERS	10	0	0
Total	44	50	70

Daily Total Trips Trend



Daily Agency trips Trend



In House Application for Generation Monitoring



Implemented in 24 NTPC Projects. Won NTPC National Professional Circle Championship for This application * Pan NTPC implementation of NEW WBES data fetching

ABT Version 6.1 (WR, ER and NER) Dated: 14/2/2023

ABT / RAMP RATE MONITORING SYSTEM

Sipat, STAGE-1

Block : 86 21:15-21:30
Time Left **13:20**

SG+AGC 1802	AG 1853
10% Dev Limit 100	Dev (MW) 51.81
DEV (%) 2.88	
INST FREQ 50.00	AVG FREQ 50.011
PRED FRQ 50.00	

UI within +/-10%

Original SG : **1856.3** Day Tot DSM (Rs)

90% SG : 1702	Avg AGC : -54.67	0.48 Lakh
110% SG : 1902	Instn AGC : -64.16	DAM : Rs. 7.60
Inst Gen : 1842.02	Predicted Gen : 1843	RTM : Rs. 12.00

Asking Rates :

49.95 Hz : 49.94 Hz	90% SG : 1908.03 MW	Block Net DSM : 0
50.03 Hz : 50.03 Hz	110% SG : 2133.03 MW	

Asking Rate For SG **1795**

RTDA Rate (P/KWh): <input type="text" value="40.34"/>	ECR : <input type="text" value="169"/>
Normative SG(MW): <input type="text" value="1856.25"/>	<input type="button" value="SAVE"/>

DSM Charges: 21888
Fuel Cost: -21888
RTDA Charges: 0

RAMP RATE PREDICTION

Required Ramp Rate : -21 (-0.07%)
Actual Ramp Rate : 29 (0.1%)
Predicted Ramp Rate : 19 (0.07%)

Todays Total Ramps : 0
Ask Rate

SG	0.5 %	1 %
SETPOINT	1801.58	
ASKING	1795	
Dev	52	

No Ramp

SYSTEM STATUS

OK Internet connection **Rev No**
OK PI Connection **184**
OK Fetching SG
Counter : 819
SG Fetching Time : 15/02/2023 09:13:33 PM
System Time : 15 Feb 2023, 09:16:43 PM
DAM : 15/02/2023 RTM : 15/02/2023

CONTROL SECTION

Start Application

 Monochromatic

Next Block Schedule

Block No	Block SG	Ramp Rate
87	1856	No Ramp

LOAD AND AGC


Unit No	Unit1	Unit2	Unit3	Tot(Nor)
Load	643	646	646	
Instn AGC	-23	-23	-23	-68.4(-64.2)
Avg AGC	-20	-19	-19	-58.3(-54.7)

Application initialized and ready to use

LAST ALERT AND SYSTEM LOGS

15/02/2023 09:15:25 PM: Error in Fetching SG got resolved
15/02/2023 09:15:20 PM: SG Updating
15/02/2023 09:15:20 PM: PI connection ok
15/02/2023 09:15:15 PM: Voice Alert : Application initialized and ready to use
15/02/2023 09:15:07 PM: Connected to PI Server
15/02/2023 09:15:03 PM: Internet connection Restored
15/02/2023 09:15:03 PM: Error in Fetching SG

Trending & Prediction for Correct Operation



3. REAL TIME TRENDS

1. REAL TIME VISUAL SUMMARY FULL DAY DSM REPORT

2. X-Y PLOT


A close-up photograph of green leaves with water droplets, set against a blurred background of a stream or waterfall. The leaves are in the foreground, with some water droplets visible on their surfaces. The background is a soft-focus view of a stream or waterfall, creating a sense of a natural, clean environment.

Environment Management

Water Conservation




Water Dashboard: Real time monitoring of water consumption.
Selected for PAN NTPC implementation



Initiatives :

- Higher Cycle of Concentration (COC ~ 5)
- Zero Liquid Discharge (ZLD)- Complied
- Water Dashboard with water balance sheet.
- Rain Water Harvesting Systems
- Performance Optimization Group (POG)
- HDPE Lining in the Reservoir.



Reservoir Seepage arrest : HDPE lining for reducing water



Total Reservoir Capacity : 4.8 MCM.

Water Saving : 4 MCM year

Water Cost saving : Rs 4.6 Cr

Pumping power Saving : 2.27 MU's / Rs 45 Lac per year.

Total Investment : Rs 27 Cr

A Floating Solar of 26 MW is under advance stage of Tending.



Rainwater Harvesting



4 Nos of Rainwater Harvesting facilities installed.

Modular, in-house design, fabrication and erection.

Rainwater collected at storm water channel – existing infrastructure.

Used in plant processes after a filtration process - gravity sand bed filter.

Total Savings:


Water Savings = 0.5 million m³




Water Consumption Benchmarking – NTPC Mouda



Mouda-Consumption Heads



Sipat-Consumption Heads



Specific water consumption : Mouda-2.16; Sipat 2.48Lt/unit

Only one reservoir in Mouda, capacity leading to reduced seepage and evaporation losses.

Dry ash utilisation 100% in Mouda due to high demand.

Special project for Dry Ash evacuation taken up at Sipat




**Special project for Dry Ash
evacuation at Sipat
New technology Use Application of
Ultrasonic Leak Detector**

Problem identification : Material Handling Valve frequent Malfunction




MHV malfunction resulted in

- Slow Dry ash evacuation and forcing wet ash handling.
- Increased water consumption and dyke filling.




3 Way Pressure Equalising Valve Non Functional

Non-Functional



Modification in Buffer Hopper 4A





Issue of poor suction vacuum in Ash evacuation header from ESP.

Air Ingress point identification by use of technology (acoustic leak detector).

Line header vacuum improvement achieved (250 mmwc), resulted in reduction of vacuum pump/FAHP running.



For Fugitive Dust control at Ash Dyke



Beshram Plantation




1.25 lakh sq mtr. area covered by Tarpaulin

Environment Management : Scrap/Waste Disposal




Segregation of wastes generated at NTPC-Sipat is being done. Waste management at NTPC-Sipat is presented as per the flow chart given below- NTPC Has sold 10.73 Cr form Scrap sales form Scrap sales.

Waste Management at Sipat Plant



Waste Management at NTPC-Sipat Township



Out of the BOX
Harnessing Hydro power from
Cooling Tower discharge

Site for the project




Site to Harness Energy- Cooling Tower Discharge Canal – Stage 1


- Location :
 - Stage 1 Cooling Tower Discharge after the bucket strainer
 - Canal dimension: 4.5m(Width) x 3.5m (Depth) x 85m (length)
 - Approx. Minimum water velocity 1m/sec



Turbine Design



Power Evacuation Plan of Fixed Type SHK Turbine Plant



Project Abstract & Feasibility



SN	Parameter	Details
1	Site location	6 no canal in stage 1 Cooling Tower discharge
2	Module in each canal	3 X 10KW
3	Capex (including Maint cost 5 yrs)	Rs 2.5 Lakh/KW (for 18 modules)
4	Capacity	180 KW (Total 6 x 3 x 10KW)
5	Annual Energy generation	1.44 MUs
6	Unit cost of Sipat (FY 2022-23 Avg)	Rs 3.17/ unit
7	Pay-back period	9.9 years
8	Useful life of Hydro turbine	40 years



Moving towards Net Zero Township




Total Installed capacity kWp (DC)	* Under installation by Station (kWpDC)	Under installation through NVVN/ NTPC RE (kWpDC)	Township Yearly Energy Consumption (MU)	Yearly Solar Generation (MU)	Energy Shortfall (MU/kWe)	Remarks
800	373	26000	9.02	0.82	8.20/940	<ol style="list-style-type: none"> 373 kW PO Awarded. Material u/transit. Floating solar(26MW) in reservoir#1B : through NTPC RE. (Award – 15Jul'24) 2.3MW Ground mounted NIT Done, BOD-22.07.24 CW Hydro turbine proposal of 1.5 MW being expedited.

	National Average*	Sipat (Total consumption)
Per Capita Electricity Consumption National per annum (in KWh)	1255	1227

Township water consumption LMC	Rainwater reuse in plant. LMC	Per capita water consumption. Lts/day	STP kLd
3.76	5.2	187	1500





Ash Utilization Plan FY'2024-25

- Total Ash generation (Projected) : 54 LM³
- AU planned for FY 24-25 : 112.9 %
- Ash Utilization Target for FY'24-25 : 60.96 LM³

Highest ever DFA (Dry Fly Ash utilization of 10.82 LMT in FY23-24, using HMDC (Hydro Mix dust conditioner).





Salient features


- **Cost:1.25 Lakh**
- **Area – 322 sq feet**
- **Ash Utilization- 40 T per house**
- **NO use of natural sand & aggregates**
- **In-house manufactured Ash products used:**
 - i. Aggregates
 - ii. Interlocking wall block
 - iii. Bottom Ash
 - iv. Paver blocks
 - v. Tiles
 - vi. Ash Based Ventilators
 - vii. Door and Window frames



LOW-COST GREEN HOUSING (LCGH)



LOW-COST GREEN HOUSING (LCGH) AN INNOVATIVE APPROACH



Layout



Bedroom



Hall



Kitchen




Toilet



Total number 13 rakes dispatched in current year to cement industries.



Geo Polymer Concrete (GPC) ROAD STATUS



GPC Road from **SAMAWESHI BHAWAN** to **Dyke-1** is **under construction**

Status:

8.6 km/11 km completed

Expected date of completion : 30-11-2024

ASH BASED VALUABLE PRODUCTS



ASH BASED VALUABLE PRODUCTS



Tetrapod



Fencing Column



Park Table



Paver Blocks



Cement Based Aggregates



ASH BASED VALUABLE PRODUCTS



NACA



HUME PIPE



GPC ROAD -ASH DYKE



PAVER BLOCKS



LWA

ASH BASED VALUABLE PRODUCTS



Boundary Wall



Nano concrete Aggregate



Paver & Wall blocks



Block production



Ash products- Displayed in exhibition



NTPC SIPAT LWA PROJECT, PILOT TO PRODUCTION



Inauguration BY Hon'ble PM



LWA Facility



Light Weight Aggregate (LWA) plant Sipat


Fly ash based Light weight aggregate as an alternate for natural stone concrete




50000 Ton capacity plant under commissioning, first lot to be produced by 30.09.23


Cost of LWA Rs 1700/Ton

Cost of Natural Stone aggregate: Rs 2000 / Ton

Trail production done on



S N	Project	Salient features	Status
1.	Geopolymer Lab Set up <ul style="list-style-type: none"> 20 TPD equipment Testing facilities 	<ul style="list-style-type: none"> In-House Production & Testing of Ash based products Development of Design Mix for new products and on going projects 	<ul style="list-style-type: none"> Infrastructure set-up completed 20 TPD machine installed and commissioned GPCA produced (20 KG) Testing of GPCA under progress Water absorption - <18%, Impact /Abrasion value-<40%, etc
2.	GPCA 	<ul style="list-style-type: none"> In house development of GPCA (Geo Polymer Coarse Aggregate) Substitute for Natural resources Huge potential for bulk ash utilization (80%) 	<p>The Projects are done to establish the techno commercial viabilities of the technology. The alternate use of Ash in making aggerate and sand will make save natural resources and will result in resolving ash disposal issue.</p>
3.	NACA 	<ul style="list-style-type: none"> In house development of NACA (NANO Concrete Aggregate) Substitute for Natural resources Potential for bulk ash utilization (70%) 	

SN	Project	Project/Benefit	Status
4.	Ash to Sand	<ul style="list-style-type: none"> • Bulk ash utilization • Conservation of natural resources • Revenue Generation 	<ul style="list-style-type: none"> • Under implementation
5.	Interlocking Wall Blocks 	<ul style="list-style-type: none"> • No need of plastering and mortar • Geopolymer/high volume fly ash based cement blocks possible 	



12000 Interlocking paver blocks used in Sipat



Ash to Sand Facility at NTPC Sipat



Pellet making machine

Pelletization of Biomass generated in plant premises – to cofire with coal (200 kg/hr)



TREE PLANTATION

Tree Plantation Since Inception : 1170801

Miyawaki Technique

✓ Growing dense forest in limited space

Plant Growth in 4 Months



Mission 1 Lakh Trees in FY 2023-24



Tree plantation Plan in FY 2023-24

1.	MGR Track (completed)	25,000
2.	DM Plant (Miyawaki) Completed	23,000
3.	Bhildi Village (Miyawaki) In progress	32,000
4.	Uchbhati village (Miyawaki) PO placed	32,000
	Total	1,12,000



800 KW ROOF TOP SOLAR PV AT NTPC SIPAT



Type	Location	Installed Capacity
Rooftop Solar PV	NTPC Sipat Hospital	50 KW
Rooftop Solar PV	Administrative Building	100 KW
Rooftop Solar PV	Solar PV at various building inside the plant	650 KW



Upcoming Solar PV in Sipat:

200 KW Solar for Township power consumption, work started.

173KW in switchyard and office building

26 MW Floating solar in reservoir are, work under award.

2 MW ground mounted solar in switchyard area planned.





Flue Gas Desulphurisation (FGD)

- FGD implementation:
 - Unit 1 & Unit 3 FGD Hot gas In Achieved
 - Unit 3 FGD Gypsum production started

Energy Savings projects implemented in last 3 years


S. No	Year	Nos of Energy Saving Projects	Investment (INR Millions)	Electrical Saving (Million kWh)	Thermal Saving (Million Kcal)	Total Saving (INR Million)
1	2020-21	11	46.5	25.3	80850	82.13
2	2021-22	7	114.78	13.64	158400	109.17
3	2022-23	5	63.0	15.94	167556	134.1
4	2023-24	6	49	32.52	26337	69

Highlight of FY 2023-24

- Repair/ Overhauling of identified mills with higher specific energy consumption
- Air ingress in duct and boiler attended during Unit overhaul
- Optimising FAHP Pump running hours.
- Stage-1 & 2 CT Fill replacement.
- Condenser water box cleaning



Condition Monitoring



Condition Monitoring Cont....



Condition Monitoring Summary			
	Equipments	Exception Reported	Due
WDA	178	0	0
DGA	71	0	0
Thermography	508	40 (Under observation)	

S.No.	Plant Sample (Equipment Name)	Testing Date	Frequency (months)	Particle Quantifier PQ index	Next Testing Due	Limits
BMD Equipments						
1	MILL -1A	15-07-2024	3	16	15-10-2024	Mill gear box oil-500 (w/o side filtration)
2	MILL -1B	15-07-2024	3	12	15-10-2024	
3	MILL -1C	15-07-2024	3	10	15-10-2024	
4	MILL -1D	15-07-2024	3	23	15-10-2024	
5	MILL -1E	15-07-2024	3	11	15-10-2024	Mill GB - 200 (with side filtration)
6	MILL -1F	15-07-2024	3	10	15-10-2024	
7	MILL -1G	15-07-2024	3	12	15-10-2024	
8	MILL -1H	15-07-2024	3	10	15-10-2024	Ball mill- 100
9	MILL -1J	15-07-2024	3	10	15-10-2024	
10	MILL -1K	15-07-2024	3	22	15-10-2024	Others (APH, Fan, etc.)-25
11	MILL -2A	15-07-2024	3	9	15-10-2024	
12	MILL -2B	15-07-2024	3	10	15-10-2024	APH GBX-50
13	MILL -2C	15-07-2024	3	11	15-10-2024	
14	MILL -2D	15-07-2024	3	10	15-10-2024	
15	MILL -2E	15-07-2024	3	11	15-10-2024	
16	MILL -2F	15-07-2024	3	15	15-10-2024	
17	MILL -2G	15-07-2024	3	10	15-10-2024	
18	MILL -2H	15-07-2024	3	12	15-10-2024	

S.No.	Equipment Name	Testing Date	Frequency (months)	OK/Not OK	Next Testing Due	Last testing observation if any
137	CF MOTOR - 1A		1			
138	CF MOTOR - 1B	2024-07-09	1			
139	VAC P/P MOTOR - 1A		1	Ok	09-08-2024	S/D
140	VAC P/P MOTOR - 1C					S/D
141	VAC P/P MOTOR - 1B	2024-07-09	1	Ok	09-08-2024	S/D
142	AWU - 1	2024-07-09	1	Ok	09-08-2024	
143	AWU - 2					
144	SEAL OIP P/P MOTOR - 1A					S/D
145	SEAL OIP P/P MOTOR - 1B	2024-07-09	1	Ok	09-08-2024	S/D
146	TDBFP - 1A ROP	2024-07-09	1	Ok	09-08-2024	
147	TDBFP - 1B MOP	2024-07-09	1	UNDER OBSERVATION	09-08-2024	PANEL SIDE : R: 69.7
148	MOP - 1A	2024-07-09	1	UNDER OBSERVATION	09-08-2024	PANEL SIDE : Y: 75.3
149	TDBFP - 1A VAC P/P - B	2024-07-09	1	Ok	09-08-2024	
150	TDBFP - 1B VAC P/P - A	2024-07-09	1	Ok	09-08-2024	
151	MDBFP - 1A AOP	2024-07-09	1	Ok	09-08-2024	
152	MDBFP - 1B AOP	2024-07-09	1	Ok	09-08-2024	
153	PRIM WATER MOTOR - 1A	2024-07-09	1	Ok	09-08-2024	PANEL SIDE : R:72.6
154	SEAL AIR FAN MOTOR - 1B	2024-07-09	1	Ok	09-08-2024	
155	SGECW MOTOR - 1B	2024-07-09	1	Ok	09-08-2024	
156	AWU - 7	2024-07-09	1	UNDER OBSERVATION	09-08-2024	PANEL SIDE : B:69.2
157	AWU - 8	2024-07-09	1	UNDER OBSERVATION	09-08-2024	MOTOR DE END : 66.3
158	PAPH MOTOR - 1A	2024-07-09	1	Ok	09-08-2024	
159	PAPH MOTOR - 1B	2024-07-09	1	Ok	09-08-2024	
160	SAPH MOTOR - 1A	2024-07-09	1	Ok	09-08-2024	
161	SAPH MOTOR - 1B	2024-07-09	1	Ok	09-08-2024	
162	AC SCANNER MOTOR	2024-07-09	1	Ok	09-08-2024	



INVENTORY MANAGEMENT

@ NTPC Sipat



Inventory Reduction Action plan - Through SAP

SN	Strategy	Action Plan	Remarks
1	Procurement after Stringent Scrutiny	Procurement being done strictly on basis of need, consumption pattern , stock in pipeline & present stock.	FY 23-24-Procurement initiated - 132 Cr/ Consumption – 166 Cr (Inventory Reduction of 34 Cr.)
2	Review of mapping of “Minimum” Critical Spares in SAP	Departments to review Inventory for critical tagging. (50 Cr inventory already tagged as critical)	Inventory is being further reviewed for critical tagging. Target 31.07.24
3	ZSPR to ZCSP Conversion & transfer of inventory	Identification of ZSPR which are currently tagged as ZCSP	13.2 Cr material identified & note initiated for conversion to ZCSP
4	Review of material issued to Vendor	Booking of Free issue material issued to Vendor after reconciliation.	Vendor store inventory has reduced from 5 Cr to 2.48 Cr.
5	Reviewing items lying in blocked codes	Inventory lying in blocked codes is being reviewed.	Blocked code amounting to 9 crs have been cleansed



Learning from last CII Event.








ENERGY EFFICIENCY VENDOR MEET




EC Projects discussed for Implementation in Vendor Meet

- Smart Air conditioning and Lighting control through Internet of Things(IOT) Applications



- IE 4 Motors for VFD Applications
- VFD in Stage 2 CEP
- CFD Analysis of Boiler Draft System



Energy Management System and SEC monitoring tools



- NTPC Sipat certified with ISO 50001:2018 certification for conformance to energy management system standards in all aspects.





thank you

